Job Name/Location: Tag No:

For: File Resubmit Date: Approval Other PO No.:

**Architect:** GC:

Mech: Engr:

Rep:

(Project Manager)

# LMU243HV

# Multi F Inverter Heat Pump Outdoor Unit

#### Performance:

| Cooling Capacity (MinRated-Max., Btu/h) | 8,400~24,000~25,000  |
|---|----------------------|
| Heating Capacity (MinRated-Max., Btu/h) | 10,080~24,600~29,000 |
| Max. Heating Capacity at 5°F (Btu/h)    | 18,400               |
| Max. Heating Capacity at 0°F (Btu/h)    | 16,730               |
| Max. Heating Capacity at -4°F (Btu/h)   | 15,400               |
| EER2                                    | 12.5                 |
| SEER2                                   | 22.5                 |
| COP                                     | 4.2                  |
| HSPF2                                   | 9.4                  |

Cooling Nominal Test Conditions: Heating Nominal Test Conditions: Indoor: 70°F DB / 60°F WB Indoor: 80°F DB / 67°F WB Outdoor: 95°F DB / 75°F WB Outdoor: 47°F DB / 43°F WB

#### **Electrical:**

| Power Supply (V/Hz/Ø)¹    | 208-230V, 60, 1 |
|---------------------------|-----------------|
| MOP (A)                   | 20              |
| MCA (A)                   | 16.0            |
| Recommended Fuse Size (A) | 20              |
| Cooling Rated Amps (A)    | 13.0            |
| Heating Rated Amps (A)    | 13.0            |
| Compressor (A)            | 12.0            |
| Fan Motor (A)             | 0.40            |
| Locked Rotor Amps (A)     | 16.0            |

MCA - Minimum Circuit Ampacity MOP - Maximum Overcurrent Protection

#### Piping:

| Refrigerant Charge (lbs.)                   | 3.97       |
|---|------------|
| Liquid Line Connection (in., O.D.)          | 1/4 x 3    |
| Vapor Line Connection (in., O.D.)           | 3/8 x 3    |
| Maximum Total Piping <sup>2</sup> (ft.)     | 230.0      |
| Min. / Max. ODU to IDU Piping (ft.)         | 9.8 / 82.0 |
| Piping Length (no add'l refrigerant, ft.)   | 98.4       |
| Maximum Elevation between ODU and IDU (ft.) | 49.2       |
| Maximum Elevation between IDU and IDU (ft.) | 24.6       |

ODU = Outdoor Unit IDU = Indoor Unit

#### Features:

- Auto operation
- Auto restart
- Inverter (variable speed compressor)
- Defrost / Deicing
- Restart delay (three [3] minutes)
- Self diagnosis
- Soft start
- Low ambient cooling down to 14°F



#### **Operating Range:**

| Cooling (°F DB) | 14 to 118 |
|-----------------|-----------|
| Heating (°F WB) | -4 to +64 |

#### **Unit Data:**

| Refrigerant Type                                   | R410A         |
|--|---------------|
| Refrigerant Control                                | EEV           |
| Sound Pressure (Cool / Heat) ±1 dB(A) <sup>3</sup> | 50 / 54       |
| Net / Shipping Weight (lbs.)                       | 101.4 / 110.2 |
| Heat Exchanger Coating                             | Gold Fin™     |
| Minimum No. of Indoor Units                        | 2             |
| Maximum No. of Indoor Units                        | 3             |

#### Compressor:

| Туре       | Twin Rotary |
|------------|-------------|
| Quantity   | 1           |
| Oil / Type | FVC68D      |

#### Fan:

| Type<br>Quantity        | Propeller                             |
|-------------------------|---------------------------------------|
| Quantity                | 1                                     |
| Motor / Drive           | Brushless Digitally Controlled/Direct |
| Max. Airflow Rate (CFM) | 1.766                                 |

#### Notes:

- 1. Acceptable operating voltage: 187V 253V.
- 2. Piping lengths are equivalent.
- 3. Sound pressure levels are tested in an anechoic chamber under ISO Standard
- 4. All power / communication cable to be minimum 14 AWG, 4-conductor, stranded, shielded or unshielded wire, and must comply with applicable local and national codes. If shielded, the wire must be grounded to the chassis at the outdoor unit only.
- 5. Power wiring size must comply with the applicable local and national codes.
- 6. This data is rated 0 ft. above sea level, with 0 ft. level difference between outdoor and indoor units, and the following refrigerant pipe lengths:

LMU183HV: 16.4 ft. x 2 = 32.8 ft. LMU243HV: 16.4 ft. x 3 = 49.2 ft.

LMU303HV: 16.4 ft. x 4 = 65.6 ft.

LMU363HV: 16.4 ft. x 4 = 65.6 ft.

All capacities are net with a combination ratio between 95 - 105%.

- 7. Must follow installation instructions in the applicable LG installation manual.
- 8. Refer to the Combintion Data Manual for combination capacity tables.
- 9. See the Performance Data Manual for sensible and latent capacities.



☐ PI-485 - PMNFP14A1 ☐ MultiSITE Comm. Mgr. -PBACNBTR0A

☐ AC Smart 5 - PACS5A000

☐ ACP 5 - PACP5A000 ☐ Power Distribution Indicator (PDI)

Premium - PQNUD1S41

☐ Mobile LGMV - PLGMVW100 ☐ Drain Pan Heater - PQSH1203 □Low Ambient Baffle Kit (Cooling operation to -4°F) - ZLABGP03A











SB\_MultiF\_LMU243HV\_2022\_07\_18\_084711

# LMU243HV

# Multi F Inverter Heat Pump Outdoor Unit





#### Notes:

- 1. Unit must be installed in compliance with the installation manual.
- 2. Unit must be grounded in accordance with the local or state regulations and applicable national codes.
- 3. All field-supplied electrical components and materials must comply with the local, state, and national codes.
- 4. Electrical characteristics must be considered for electrical work and design. The capacity of power cable and circuit breaker for the outdoor unit must follow local, state, national, and manufacturer requirements.

(BACK)

5. For LMU183HV Unit, ports A and B are available.

17-11/16

6. For LMU243HV Unit, ports A, B, and C are available.

Job Name/Location:

Tag No.:

| Date: |      |  |
|-------|------|--|
| РО    | No.: |  |

For:

File

Approval

Resubmit Other\_

**Architect:** 

GC:

Engr:

Mech:

Rep:

(Project Manager)

# PT-QAGW0

2' x 2' Cassette Panel


For Multi V™/Single-Zone /Multi F 4-Way Ceiling-Cassette Indoor Units







### **Unit Data:**

| Color                           | White                       |
|---------------------------------|-----------------------------|
| RAL Color Code                  | RAL 9003                    |
| RGB Color Code                  | 236 - 236 - 231             |
| Material                        | ABS XG571                   |
| Net Dimensions (W x H x D, in.) | 24-13/32 x 1-3/8 x 24-13/32 |
| Shipping Dimensions             |                             |
| (W x H x D, in.)                | 27-/32 x 5 x 26-1/2         |
| Net Weight (lbs.)               | 6.3                         |
| Shipping Weight (lbs.)          | 8.6                         |
| Display LED Color               | Green                       |
| Filter                          | Washable                    |







| Job Name/Location: |       | Tag #:   |          |  |
|--------------------|-------|----------|----------|--|
| Date:              | For:  |          | Resubmit |  |
| PO No.:            |       | Approval | Other    |  |
| Architect:         | GC:   |          |          |  |
| Engr:              | Mech: |          |          |  |
| Rep:               |       |          |          |  |

(Project Manager)

# LMCN078HV

Multi F Ceiling Cassette Indoor Unit 7,000 Btu/h



#### Performance:

(Company)

| Nominal Cooling Capacity (Btu/h) | 7,000 |
|----------------------------------|-------|
| Nominal Heating Capacity (Btu/h) | 8,100 |

Cooling Nominal Test Conditions: Indoor: 80°F DB / 67°F WB Outdoor: 95°F DB / 75°F WB

Heating Nominal Test Conditions: Indoor: 70°F DB / 60°F WB Outdoor: 47°F DB / 43°F WB

#### Electrical:

| Power Supply (V¹/Hz/Ø) | 208-230/60/1 |
|------------------------|--------------|
| Rated Amps (A)         | 0.25         |

## Piping:

| Installed Liquid Pipe (in., O.D.) | ø1/4       |
|-----------------------------------|------------|
| Installed Vapor Pipe (in., O.D.)  | ø3/8       |
| Liquid Connection (in., O.D.)     | ø1/4       |
| Vapor Connection (in., O.D.)      | ø3/8       |
| Drain (in., O.D. / I.D.)          | 1-1/4, 1   |
| Temperature Sensor                | Thermistor |

#### **Controls Features:**

- Two thermistor control
- 24-Hour on / off timer
- Auto operation
- Auto restart
- · Chaos swing
- Control lock function
- Drain pump

- Group control
- Inverter (variable speed fan)
- Jet cool
- · Compatible with accessory Wi-Fi module

### **Included Accessories:**

• Wireless Remote Controller — AKB73757604

#### **Required Accessories:**

- $\square$  Grille Kit (27-9/16" x 27-9/16") PT-UQC, or
- ☐ Grille Kit (24-7/16" x 24-7/16") PT-QCHW0

#### **Optional Accessories:**

- ☐ MultiSITE™ CRC1 Controller PREMTBVC0
- ☐ MultiSITE™ CRC1+ Controller PREMTBVC1
- ☐ Simple Remote Controller PREMTC00U
- ☐ Premium Remote Controller PREMTA000 ☐ Remote Temperature Button Sensor - ZRTBS01
- ☐ Simple Dry Contact (1 contact, 24 VAC external power) PDRYCB100
- ☐ Dry Contact for Third Party Thermostat PDRYCB300
- ☐ Dry Contact for Economizer PDRYCB400
- ☐ Auxiliary Heater Kit PRARH1
- ☐ Wi-Fi Module PWFMDD200

#### **Entering Mixed Air:**

| Cooling (°F WB) | 57 ~ 77 |
|-----------------|---------|
| Heating (°F DB) | 59 ~ 81 |

#### **Unit Data:**

| Refrigerant Type                          | R410A               |
|---|---------------------|
| Refrigerant Control                       | EEV                 |
| Sound Pressure (H/M/L) dB(A) <sup>2</sup> | 31 / 27 / 24        |
| Primary Filter <sup>3</sup>               | Washable Pre-filter |
| Net Weight (lbs.)                         | 26                  |
| Shipping Weight (lbs.)                    | 31                  |
| Grille Net Weight (lbs.)                  | 7                   |
| Grille Shipping Weight (lbs.)             | 9                   |

#### Fan:

| Туре                 | Turbo                                 |
|----------------------|---------------------------------------|
| Quantity             | 1                                     |
| Motor/Drive          | Brushless Digitally Controlled/Direct |
| Air Flow H/M/L (CFM) | 265 / 212 / 177                       |

#### Notes:

- NOLES:

  1. Acceptable operating voltage: 187V-253V.

  2. Sound Pressure levels are tested in an anechoic chamber under ISO Standard 3745.

  3. Removable Washable Filter size: 14" x 14" x 1".

  4. See Engineering Manual for sensible and latent capacities.

  5. All communication / connection (power) cable from the outdoor unit to the indoor unit is field supplied and must be a minimum of four-conductor, 18 AWG, stranded, shielded or unshielded (if shielded, it must be grounded to the chassis of the outdoor unit only), and must comply with applicable local and national codes.

  6. Power wiring cable size must comply with the applicable local and national code.

  7. The indoor unit comes with a dry helium charge.
- 8. Corresponding refrigerant piping length is in accordance with standard length of each outdoor unit and the level difference is 0 ft. All capacities are net with a combination ratio between 95 105%.

  9. Must follow installation instructions in the applicable LG installation manual.







| Job | Name. | /Location: |
|-----|-------|------------|
|     |       |            |

# LMCN078HV

Multi F Ceiling Cassette Indoor Unit 7.000 Btu/h



PO No.:

