






Back of tub designed to accommodate rear drain.

Parisian® 2

| MODEL 178 | | | |
|---|--------------------------|--|--|
| 72" x 40" x 23.375" | | | |
| FREESTANDING 87 gal to overflow | | | |
| Acrylic CXL™ | DoloMatte™ | | |
| 280 lbs / 127 kg <sc< td=""><td colspan="3">SOAKER> 315 lbs / 143 kg</td></sc<> | SOAKER> 315 lbs / 143 kg | | |
| Part of the state | | | |

Filling this tub to the maximum may require an above average size or dedicated water heater.




IMPORTANT:

Must have access to the drain from underneath the tub for installation and servicing.

Drain Rough-In Measurements

| Α | В | С |
|-------|-------|-------|
| 41/2" | 91/4" | 43/4" |



Requires use of a wall-mounted or freestanding tub filler. Shown with Air Massage Package.

117 20" 23%" 163/41

ELECTRICAL COMPONENTS & SPECIFICATIONS

| Hydrotherapy Package | Components Included | 110V GFCI |
|----------------------|------------------------------|-----------|
| Air Massage | heated blower | 1-15 amp |
| Air Massage Elite | heated blower, chromatherapy | 1-15 amp |

Electrical requirements may change with the addition of optional therapy components.

See specific option details or installation information.

CSA Certified C/US; ANSI Z124.1 and ANSI 112.19.7

IMPORTANT ORDERING & INSTALLATION INFORMATION:

- Before ordering or installing, please consider future access to equipment.
- · No access panel. Tub features factory installed overflow with toe tap drain.
- Air baths require job site preparations for remote mounting the blower and required check valve. Check valve must be installed higher than the rim of the tub.
- Hydrotherapy equipment may ship loose for remote installation depending on tub model. See package content on the following page for details.
- Radiance placed on floor locations will affect placement of air jets.
- Faucet valves cannot be installed on this tub model.
- All tubs are in accordance with CSA B45.5/IAPMO Z124 standard and compliant with ASTM C 1028-07 coefficient of friction. Dolomatte meets ANSI A137.1/A326.3 coefficient of friction and AS HB198:2014 pendulum slip resistance testing.

See the Installation & Operation Manual for more details. MTI's Customer Service: Monday-Friday 8am-6pm EST 800-783-8827 or service@mtibaths.com



©2022 by MTI Baths, Inc. Modification Rights Reserved

Before discarding tub crate, check for accessories that may be packaged inside.
 All product measurements are +1/2".
 Specifications and configurations are subject to change without notice.
 Measurements herein supersede all others published prior to publication date below.

Parisian® 2 MODEL 178 72" x 40" x 23.375"

| Hydrotherapy Package Contents | | Acrylic CXL™ | | DoloMatte™ | |
|-------------------------------|---|--------------|----------|------------|----------|
| | | Part # | MSRP | Part # | MSRP |
| Soaker | Soaking bath - no jets; includes a pre-leveled foam base and factory-installed overflow with toe-tap drain kit in chrome. | S178 | \$11,705 | S178DM | \$12,505 |
| Air Massage | 20 air jets, heated air blower, pre-leveled foam base and factory-installed overflow with toe-tap drain kit in chrome. Blower and control boxes must be remote located. | AST178 | \$15,355 | AST178DM | \$16,155 |
| Air Massage Elite | 30 air jets, heated air blower, Chromatherapy LED lighting, Spa Mode, pre-leveled foam base and factory-installed overflow with toe-tap drain kit in chrome. Blower and control boxes must be remote located. | AE178 | \$17,255 | AE178DM | \$18,055 |

RECOMMENDED SENSORY THERAPIES

| Chr | oma | ther | ару |
|-----|-----|------|-----|
|-----|-----|------|-----|

(LE) **\$800** underwater lighting 2 LED lights included

Audiotherapy

(STEREOBT) **\$1,390** 2 transducers with bluetooth and amplifier (BTREMOTE) **\$600** bluetooth remote

(STEREOH202) **\$1,575** 4 transducers amplifier not included

Thermaltherapy

(RAD100) **\$1,595** Radiance® 2 heated zones included

Options Must be ordered at time of purchase.

Standard Colors White (CWH) *Please call for availability of special colors.*

Quick Ship reduces lead time (QSPRI) \$430

Please call for availability

Textured, Slip-Resistant Bottom (TXTBTM) \$105

Accessories

Pillows from \$180

Teak Bath Mat (TKMAT3018) \$815

Custom sizes also available. Contact MTI for details and pricing.

Floor-Mounted High-Flow Tub Filler two designs available

Contemporary

Chrome (FILLC) \$1,480

Brushed Nickel (FILLBN) **\$1,710**

Traditional

Chrome (FILLTC) \$1,505

Brushed Nickel (FILLTBN) \$1,745

Faucet Stand SculptureStone® Standard

Small 3-hole capacity **14**½" w x **21**¾" h Matte (STAND) **\$725** **Large** 5-hole capacity **22" w x 21¾" h**Matte (STANDL) **\$855**

+\$430 gloss finish upcharge (SSGLOSSSNK)

Drains & Overflow Kits Must be ordered at time of purchase

Toe Tap with Round Overflow – PVC Drain Kit

Overflow is factory installed Chrome (WOTTC) included

Brushed Nickel (WOTTBNU) substitute free of charge

Finish Upcharge

White (WOTTWU) \$35 Polished Nickel (WOTTPNU) \$60 Oil-Rubbed Bronze⁺ (WOTTORU) \$65 Special Finishes⁺ (WOTTSFU) \$790