American Standard

Style That Works Better

#### CLINIC SERVICE SINK

- Vitreous china
- Wall-hung
- Flushing rim
- Blow-out flushing action
- 1-1/2" brass top spud
- 9512.013 Service sink

## **Available Components:**

- **037640-0020A** Cast metal loose strainer
- 7832017.075 Stainless steel 10" (254mm) guard (3 shown)

## **Nominal Dimensions:**

622 x 508mm (24-1/2" x 20")

## NOTE:

- 1) Recommended minimum working pressure: 25 psi at valve when flushing
- 2) Waste outlet piping: 4" preferred 3" acceptable

# **Compliance Certifications -**Meets or Exceeds the Following Specifications:


ASME A112.19.2 for Vitreous China Fixtures

#### To Be Specified:

- □ Faucet: 8345.100 wall mounted with 152mm (6") wrist handles
- □ Alternative Faucet:
- Flush Valve: Sloan Royal 117H
- Alternate Flush Valve
- □ Rim Guard: Stainless Steel 279mm (11") 7832.017 (3) if required
- Waste outlet seal (neoprene or graphite-felt)
- Bedpan Cleanser:
  - □ 7880.024
  - □ 7880.083
  - **7880.091**
- Strainer: 037640-0020A Metal Loose Strainer
- □ Carrier Fitting (by others):

Available in White Only





NOTES

WASTE OUTLET SEAL RING MUST BE NEOPRENE OR GRAPHITE-FELT

WASTE OUTLET SEAL HING MOST BE NEOPRENE OF GRAPHITE-FELT (WAX RING NOT RECOMMENDED). TO COMPLY WITH AREA CODE GOVERNING THE HEIGHT OF VACUUM BREAKER ON FLUSH VALVE, THE PLUMBER MUST VERIFY DIMEN-SIONS SHOWN FOR SUPPLY ROUGHING. CARRIER FITTING AS REQUIRED TO BE FURNISHED BY OTHERS. SUGGESTED 1/16 CLEARANCE BETWEEN FACE OF WALL AND BACK OF

SINK

FLUSH VALVE AND FITTINGS NOT INCLUDED AND MUST BE ORDERED SEPARATELY PROVIDE SUITABLE REINFORCEMENT FOR ALL WALL SUPPORTS.

**IMPORTANT**: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.